

ADDENDUM NO. 2

ALLEGAN COUNTY ROAD COMMISSION

2023 PRIMARY HOT MIX ASPHALT PAVING

MARCH 15, 2023

Addendum No. 2 to the Proposal and Specifications for 2023 Primary Hot Mix Asphalt Paving for the Allegan County Road Commission, as prepared by the Allegan County Road Commission for the March 15, 2023, bid letting. The purpose of this addendum is to add the following project:

**6. PH 300064 - CHESHIRE TOWNSHIP – 42<sup>nd</sup> Street, 108<sup>th</sup> Avenue to 112<sup>th</sup> Avenue – 2.00 miles**

The work will consist of conditioning the aggregates base and drives. Then place an HMA, 4EL leveling course with an average yield of 220 lb/syd, followed by a HMA, 4EL surface course with an average yield of 220 lb/syd. Gravel shoulders and approaches will then be placed from the POB to POE. Pavement markings will then be placed from the POB to POE.

The Contractor hereby acknowledges receipt of this Addendum No. 1 and shall include a signed copy with his bid.

Contractor: \_\_\_\_\_

Signature: \_\_\_\_\_

Printed Name: \_\_\_\_\_

Title: \_\_\_\_\_

Date: \_\_\_\_\_

6. PH 300064 – CHESHIRE TOWNSHIP – 42<sup>nd</sup> Street, 108<sup>th</sup> Ave. to 112<sup>th</sup> Ave. 2.00 miles

BID AND AWARD

Date: \_\_\_\_\_

Board of County Road Commissioners  
of Allegan County  
1308 Lincoln Road  
Allegan, MI 49010

Gentlemen:

The undersigned has examined the plans, specifications, and location of the work described herein and is fully informed as to the nature of the work and the conditions relating to its performance and understands that the quantities shown in the estimate are approximate only and are subject to either increase or decrease; and hereby proposes to furnish all necessary machinery, tools, apparatus, and other means of doing the work, do all the work, furnish all the materials except as otherwise specified herein, and, for the unit prices named in the accompanying unit price schedule, to complete work in strict accordance with the plans and specifications therefore.

The undersigned further proposes to do such extra work as may be ordered by you, prices for which are not included in the itemized bid, compensation therefore to be made on the basis agreed upon before such extra work is begun.

The undersigned agrees to complete all items of work on or before **August 25, 2023.**

The undersigned encloses a certified check, cashier's check, or Bid Bond representing 5% of the bid, in the amount of \$ \_\_\_\_\_, payable to the Allegan County Road Commission as a guarantee of good faith. If the contract is awarded to the undersigned and the undersigned fails to furnish satisfactory bonds to the Road Commission within fifteen (15) days after being given notice of award, said check will be forfeited to the Allegan County Road Commission as liquidated damage.

ALLEGAN COUNTY ROAD COMMISSION

SPECIAL PROVISIONS

FOR

6. PH 300064 – CHESHIRE TOWNSHIP – 42<sup>nd</sup> Street, 108<sup>th</sup> Ave. to 112<sup>th</sup> Ave. 2.00 miles

SCOPE OF THE WORK

The work will consist of conditioning the aggregates base and drives. Then place an HMA, 4EL leveling course with an average yield of 220 lb/syd, followed by a HMA, 4EL surface course with an average yield of 220 lb/syd. Gravel shoulders and approaches will then be placed from the POB to POE. Pavement markings will then be placed from the POB to POE.

HMA Widths:

<u>Station</u>	<u>HMA Width</u>	<u>Shoulder Width</u>
POB to POE	32'	1' Rt & Lt

Miscellaneous Items of Work Quantity

<u>Station</u>	<u>Description</u>	<u>Dimensions</u>	<u>House</u>
10+00	Centerline of 108 <sup>th</sup> Street (Reference)	#	
10+15	POB, Pavt for Butt Joints, Rem	55'x18'	
49+50 Lt	Begin HMA Valley Gutter		
49+50 Rt	Begin HMA Valley Gutter		
51+70 Rt	End HMA Valley Gutter		
53+50 Lt	End HMA Valley Gutter		
62+80	Intersection of 42 <sup>nd</sup> & 110 <sup>th</sup>		
70+00 Lt	Begin HMA Valley Gutter		
72+50 Lt	End HMA Valley Gutter		
117+72	POE, Pavt for Butt Joints, Rem	55'x18'	

**ITEMIZED UNIT PRICE BID SCHEDULES FOR  
ALLEGAN COUNTY PRIMARY HOT MIX ASPHALT PAVING**

**6. PH 300064 – CHESHIRE TOWNSHIP – 42<sup>nd</sup> Street, 108<sup>th</sup> Ave. to 112<sup>th</sup> Ave. 2.00 miles**

ITEM OF WORK	QUANTITY	UNIT PRICE	TOTAL
HMA, 4E1, Mod (64-28)	8,500 Ton		
Monument Box, Adjust	1 Ea		
Pavt Mrkg, Type NR, Tape, 4-inch, Yellow, Temp	117 Sta		
Pavt for Butt Joints, Rem	225 Syd		
Aggregate Base Conditioning	117 Sta		
Shoulder & Approach, CI II, LM	700 Cyd		
Flag Control	1 LS		
Traffic Control Devices	1 LS		
Pavt Mrkg, Waterborne, 4-inch, Yellow	8,000 Ft		
Pavt Mrkg, Waterborne, 4-inch, White	21,200 Ft		

TOTAL OF BID \$ \_\_\_\_\_

SIGNED: \_\_\_\_\_ DATE: \_\_\_\_\_  
(Bidder)