

**ADDENDUM NO. 1**

**ALLEGAN COUNTY ROAD COMMISSION  
COUNTY PRIMARY HOT MIX ASPHALT PAVING  
PRIMARY MAINTENANCE**

***April 1, 2015***

Addendum No. 1 to the Proposal and Specifications for Local Road Bituminous Surface for the Allegan County Road Commission, as prepared by the Allegan County Road Commission for the April 15, 2015 bid letting. The purpose of this addendum is to add an additional location and updated itemized unit price bid schedule to the following project:

- 8. PRIMARY MAINTENANCE – Spot milling and paving in Manlius, Allegan, Leighton and Otsego Townships.**

**\*Cross out pages 56-59 in the Proposal and Specifications and use the following pages to submit a bid for the revised project. An additional location in Salem Township on 138<sup>th</sup> Avenue is added to the locations and the additional quantities are represented in the bid schedule.**

The Contractor hereby acknowledges receipt of this Addendum No. 1 and shall include a signed copy with his bid.

*Contractor:* \_\_\_\_\_

*By:* \_\_\_\_\_

*Printed Name:* \_\_\_\_\_

*Title:* \_\_\_\_\_

*Date:* \_\_\_\_\_

8. PRIMARY MAINTENANCE – Spot milling and paving in Manlius, Allegan, Leighton, Otsego, and Salem Townships.

BID AND AWARD

Date: \_\_\_\_\_

Board of County Road Commissioners  
of Allegan County  
1308 Lincoln Road  
Allegan, MI 49010

Gentlemen:

The undersigned has examined the plans, specifications, and location of the work described herein and is fully informed as to the nature of the work and the conditions relating to its performance and understands that the quantities shown in the estimate are approximate only and are subject to either increase or decrease; and hereby proposes to furnish all necessary machinery, tools, apparatus, and other means of doing the work, do all the work, furnish all the materials except as otherwise specified herein, and, for the unit prices named in the accompanying unit price schedule, to complete work in strict accordance with the plans and specifications therefore.

The undersigned further proposes to do such extra work as may be ordered by you, prices for which are not included in the itemized bid, compensation therefore to be made on the basis agreed upon before such extra work is begun.

The undersigned agrees to complete all items of work on or before September 25, 2015. This project will be ready to pave on or about May 4, 2015.

The undersigned encloses a certified check, cashier's check, or Bid Bond representing 5% of the bid, in the amount of \$ \_\_\_\_\_, payable to the Allegan County Road Commission as a guarantee of good faith. If the contract is awarded to the undersigned and the undersigned fails to furnish satisfactory bonds to the Road Commission within fifteen (15) days after being given notice of award, said check shall be forfeited to the Allegan County Road Commission as liquidated damage.

ALLEGAN COUNTY ROAD COMMISSION

SPECIAL PROVISIONS

FOR

8. PRIMARY MAINTENANCE – Spot milling and paving in Manlius, Allegan, Leighton, Otsego, and Salem Townships.

HMA 4C, MOD

COLD MILLING HMA SURFACE

PAVEMENT MARKING, WATERBORNE, 4 INCH, WHITE

PAVEMENT MARKING, WATERBORNE, 4 INCH, YELLOW

PAVEMENT MARKING, TEMPORARY

FLAG CONTROL

TRAFFIC CONTROL DEVICES

SCOPE OF THE WORK

The work will consist of preparing the existing surface, cold milling the existing HMA surface, then placing a HMA 4C, Mod leveling and/or surface course at various widths at an average yield of 220 lb/syd. Any shoulder gravel required will be placed by the Allegan County Road Commission. A leveling course may be required at the 128<sup>th</sup> Avenue location.

The work shall also include furnishing and applying Bond Coat (included in HMA items), MDOT Standard Specifications MS-2a or SS-1h before placing both HMA courses. Bond Coat will be placed at the rate of 0.05 – 0.10 gallons per square yard prior to placing HMA.

Intersections, driveway approaches, and valley curb are included in the bid quantities for HMA items. All approach HMA and valley curb will be paid for as HMA 4C, Mod.

Location and Description:

Milling and Paving Width

128 <sup>th</sup> Avenue – East of 60 <sup>th</sup> Street, both lanes, 400' x 34'	34' HMA
Dumont Road – 3,400' north of 118 <sup>th</sup> Avenue, east lane, 200' x 16'	16' HMA
146 <sup>th</sup> Avenue – 1,900' east of Division, both lanes, 100' x 30'	30' HMA
102 <sup>nd</sup> Avenue – 1,290 east of 23 <sup>rd</sup> Street, north lane, 14' x 50'	14' HMA
Monroe Road – 700' west of 34 <sup>th</sup> Street, both lanes, 32' x 100'	Mill Only
138 <sup>th</sup> Avenue – 1,200' east of 28 <sup>th</sup> Street, both lanes, over bridge, 32' x 200'	32' HMA

8. PRIMARY MAINTENANCE – Spot milling and paving in Manlius, Allegan, Leighton and Otsego Townships.

ALLEGAN COUNTY ROAD COMMISSION  
ALLEGAN, MICHIGAN

ITEMIZED UNIT PRICE BID SCHEDULE

ITEM OF WORK	QUANTITY	UNIT PRICE	TOTAL
HMA 4C, Mod	400 Ton		
Cold Milling HMA Surface	3,360 Syd		
Pavement Marking, Temporary	10 Sta		
Flag Control	1 LS		
Traffic Control Devices	1 LS		

TOTAL OF BID \$ \_\_\_\_\_

SIGNED: \_\_\_\_\_  
(Bidder)

DATE: \_\_\_\_\_

